

TACKER SYSTEM

Screeded Floor Construction - Product Datasheet

This system is a quick and flexible system, providing an even and effective form of heating within a screeded floor build up. UFH pipework is typically clipped to a PIR sheet insulation.

Tacker clips are fed from a specialist tool through into the PIR insulation - these staples are barbed to give a good fixing that will withstand the flex of the pipe.

We recommend that the screeding process is scheduled to follow shortly after installation to avoid leaving the system vulnerable to damage. If a liquid screed is used, the insulation must be sealed to provide a watertight base.

